

AD-A143 053

NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS  
MALTBY LAKE DAM NUMBE. (U) CORPS OF ENGINEERS WALTHAM  
MA NEW ENGLAND DIV AUG 79

1/1

UNCLASSIFIED

F/G 13/13

NL





MICROCOPY RESOLUTION TEST CHART  
NATIONAL BUREAU OF STANDARDS-1963-A

AD-A143 053

①

CONNECTICUT COASTAL BASIN  
WEST HAVEN, CONNECTICUT  
**MALTBY LAKE DAM No. 1**  
**CT 00111**

PHASE I INSPECTION REPORT  
NATIONAL DAM INSPECTION PROGRAM



**DTIC**  
**ELECTE**  
JUL 12 1984  
**S** **E** **D**

DTIC FILE COPY

DEPARTMENT OF THE ARMY  
NEW ENGLAND DIVISION, CORPS OF ENGINEERS  
WALTHAM, MASS. 02154

AUGUST, 1979

This document has been approved  
for public release and sales its  
distribution is unlimited.

84 07 11 061

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER CT 00111	2. GOVT ACCESSION NO. AD-A143 053	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Conn. Coastal Basin West Haven, Conn., Maltby Lake Dam No.1 NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS		5. TYPE OF REPORT & PERIOD COVERED INSPECTION REPORT
7. AUTHOR(s) U.S. ARMY CORPS OF ENGINEERS NEW ENGLAND DIVISION		6. PERFORMING ORG. REPORT NUMBER
9. PERFORMING ORGANIZATION NAME AND ADDRESS		8. CONTRACT OR GRANT NUMBER(s)
11. CONTROLLING OFFICE NAME AND ADDRESS DEPT. OF THE ARMY, CORPS OF ENGINEERS NEW ENGLAND DIVISION, NEDED 424 TRAPELO ROAD, WALTHAM, MA. 02254		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		12. REPORT DATE August 1979
		13. NUMBER OF PAGES 60
		15. SECURITY CLASS. (of this report) UNCLASSIFIED
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report) APPROVAL FOR PUBLIC RELEASE: DISTRIBUTION UNLIMITED		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report) DTIC ELECTE JUL 12 1984 E		
18. SUPPLEMENTARY NOTES Cover program reads: Phase I Inspection Report, National Dam Inspection Program; however, the official title of the program is: National Program for Inspection of Non-Federal Dams; use cover date for date of report.		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) DAMS, INSPECTION, DAM SAFETY, Conn. Coastal Basin West Haven, Conn. Maltby Lake Dam		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) This 26 ft. high water supply facility dam consists of two main sections. The upstream section is an earthfill dam built in 1862. The downstream part, built in 1900, is a stone masonry gravity section. The area between the two sections was filled in 1900 with a well-compacted clayey soil adjacent to the older upstream fill material. The spillway is a 21.5' ft. long broad-crested stone masonry weir discharging to a concrete and stone channel which leads to a concrete arch culvert under Conn. Route 34 immediately downstream of the dam.		





DEPARTMENT OF THE ARMY  
NEW ENGLAND DIVISION, CORPS OF ENGINEERS  
424 TRAPELO ROAD  
WALTHAM, MASSACHUSETTS 02154

REPLY TO  
ATTENTION OF:  
NEDED

NOV 28 1979

Honorable Ella T. Grasso  
Governor of the State of Connecticut  
State Capitol  
Hartford, Connecticut 06115

Dear Governor Grasso:

Inclosed is a copy of the Maltby Lake Dam No. 1 Phase I Inspection Report, which was prepared under the National Program for Inspection of Non-Federal Dams. This report is presented for your use and is based upon a visual inspection, a review of the past performance and a brief hydrological study of the dam. A brief assessment is included at the beginning of the report. I have approved the report and support the findings and recommendations described in Section 7 and ask that you keep me informed of the actions taken to implement them. This follow-up action is a vitally important part of this program.

A copy of this report has been forwarded to the Department of Environmental Protection, the cooperating agency for the State of Connecticut. In addition, a copy of the report has also been furnished the owner, New Haven Water Company.

Copies of this report will be made available to the public, upon request, by this office under the Freedom of Information Act. In the case of this report the release date will be thirty days from the date of this letter.

I wish to take this opportunity to thank you and the Department of Environmental Protection for your cooperation in carrying out this program.

Sincerely,

MAX B. SCHEIDER  
Colonel, Corps of Engineers  
Division Engineer

Incl  
As stated

CONNECTICUT COASTAL BASIN  
WEST HAVEN, CONNECTICUT  
**MALTBY LAKE DAM No. 1**  
**CT 00111**



**PHASE I INSPECTION REPORT**  
**NATIONAL DAM INSPECTION PROGRAM**



DEPARTMENT OF THE ARMY  
NEW ENGLAND DIVISION, CORPS OF ENGINEERS  
WALTHAM, MASS. 02154

Accession For		
NTIS GRA&I	<input checked="" type="checkbox"/>	
DTIC TAB	<input type="checkbox"/>	
Unannounced	<input type="checkbox"/>	
Justification		
By		
Distribution/		
Availability Codes		
Dist	Avail and/or Special	
A-1		

AUGUST, 1979

## BRIEF ASSESSMENT

### PHASE IN INSPECTION REPORT

#### NATIONAL PROGRAM OF INSPECTION OF DAMS

Name of Dam:	MALTBY LAKE DAM NO. 1
Inventory Number:	CT-111
State Located:	CONNECTICUT
County Located:	NEW HAVEN
Town Located:	WEST HAVEN
Stream:	TRIBUTARY TO WEST RIVER
Owner:	NEW HAVEN WATER COMPANY
Date of Inspection:	MAY 1, 1979
Inspection Team:	PETER M. HEYNEN
	CALVIN GOLDSMITH
	MIRON PETROVSKY
	GEORGE STEPHENS
	CARL BENKSON

This 26 foot high water supply facility dam consists of two main sections. The upstream section is an earthfill dam built in 1862. The downstream part, built in 1900, is a stone masonry gravity section. The area between the two sections was filled in 1900 with a well-compacted clayey soil adjacent to the older upstream fill material. The spillway is a 21.5' foot long broad-crested stone masonry weir discharging to a concrete and stone channel which leads to a concrete arch culvert under Connecticut Route 34 immediately downstream of the dam. The outlets consist of a 16 inch supply main and a 10 inch low level outlet, both of which are gated on the downstream side of the dam, the 16 inch pipe at a gatehouse at the toe of the dam, and the 10 inch by a gate in a manhole at the toe of the dam. In addition there is a 20 inch pipe through the dam which carries water from the upper Maltby Lake No. 2 to the downstream gatehouse. From the gatehouse, a water line runs to the filtration plant on the opposite side (southeast) of Route 34.


Based upon the visual inspection at the site and past performance, the dam appears to be in good condition. No evidence of instability was observed in the downstream masonry section, the upstream earthfill section, or any appurtenances.

Based upon the size (Small) and hazard classification (High) of the dam in accordance with Corps of Engineers guidelines, the test flood, will be equivalent to one-half the Probable Maximum Flood (PMF). Peak inflow to the reservoir is 1450 cfs; peak outflow is 1220 cfs with the dam overtopped 0.6 feet. Based upon our hydraulic computations, the spillway capacity is 520 cfs without the swale overflow, which is equivalent to 43% of the routed test flood outflow.


It is recommended that the owner initiate further studies to be undertaken to perform a more refined hydraulic/-hydrologic study to determine more accurately the spillway capacity and potential for overtopping. Recommendations should then be made by the engineer and implemented by the owner to increase the project discharge capacity.

It is further recommended that a registered professional engineer qualified in dam design develop recommendations for the raising of a low swale, located to the right of the dam, to the elevation of the top of the dam.

The above recommendations, and any required remedial measures, are discussed in Section 7, and should be instituted by the owners within two years of their receipt of this report.


  
Peter M. Heynen, P.E.  
Project Manager  
Cahn Engineers, Inc.





  
Edgar B. Vinal Jr., P.E.  
Senior Vice President  
Cahn Engineers, Inc.




This Phase I Inspection Report on Maltby Lake No. 1 Dam has been reviewed by the undersigned Review Board members. In our opinion, the reported findings, conclusions, and recommendations are consistent with the Recommended Guidelines for Safety Inspection of Dams, and with good engineering judgment and practice, and is hereby submitted for approval.

  
JOSEPH W. FINEGAN, JR., MEMBER  
Water Control Branch  
Engineering Division

  
JOSEPH A. MCELROY, MEMBER  
Foundation & Materials Branch  
Engineering Division

  
CARNEY M. TERZIAN, CHAIRMAN  
Chief, Structural Section  
Design Branch  
Engineering Division

APPROVAL RECOMMENDED:

  
JOE B. FRYAR  
Chief, Engineering Division



## PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I Investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspection. Detailed investigation, and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I Investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam would necessarily represent the condition of the dam at some point in the future. Only through continued care and inspection can there be any chance that unsafe conditions will be detected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the Spillway Test Flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. Because of the magnitude and rarity of such a storm event, a finding that a spillway will not pass the test flood should not be interpreted as necessarily posing a highly inadequate condition. The test flood provides a measure of relative spillway capacity and serves as an aid in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.



## TABLE OF CONTENTS

	<u>Page</u>
Letter of Transmittal	i
Brief Assessment	iii
Review Board Signature Page	iv
Preface	v
Table of Contents	viii
Overview Photo	ix
Site Location Plan	

### SECTION 1: PROJECT INFORMATION

1.1 <u>General</u> .....	1
a. Authority	
b. Purpose of Inspection Program	
c. Scope of Inspection Program	
1.2 <u>Description of Project</u> .....	2
a. Location	
b. Description of Dam and Appurtenances	
c. Size Classification	
d. Hazard Classification	
e. Ownership	
f. Operator	
g. Purpose of Dam	
h. Design and Construction History	
i. Normal Operational Procedures	
1.3 <u>Pertinent Data</u> .....	4
a. Drainage Area	
b. Discharge at Damsite	
c. Elevations	
d. Reservoir	
e. Storage	
f. Reservoir Surface	
g. Dam	
h. Diversion and Regulatory Tunnel	
i. Spillway	
j. Regulating Outlets	

## SECTION 2: ENGINEERING DATA

2.1 <u>Design</u> .....	8
a. Available Data	
b. Design Features	
c. Design Data	
2.2 <u>Construction</u> .....	8
a. Available Data	
b. Construction Considerations	
2.3 <u>Operations</u> .....	8
2.4 <u>Evaluation</u> .....	8
a. Availability	
b. Adequacy	
c. Validity	

## SECTION 3: VISUAL INSPECTION

3.1 <u>Findings</u> .....	9
a. General	
b. Dam	
c. Appurtenant Structures	
d. Reservoir Area	
e. Downstream Channel	
3.2 <u>Evaluation</u> .....	10

## SECTION 4: OPERATIONAL PROCEDURES

4.1 <u>Regulatory Procedures</u> .....	12
4.2 <u>Maintenance of Dam</u> .....	12
4.3 <u>Maintenance of Operating Facilities</u> ..	12
4.4 <u>Description of Any Warning System</u> <u>in Effect</u> .....	12
4.5 <u>Evaluation</u> .....	12

## SECTION 5: HYDRAULIC/HYDROLOGIC

5.1 <u>Evaluation of Features</u> .....	13
a. General	
b. Design Data	
c. Experience Data	
d. Visual Observations	
e. Test Flood Analysis	
f. Dam Failure Analysis	

## SECTION 6: STRUCTURAL STABILITY


6.1 <u>Evaluation of Structural Stability...</u>	15
a. Visual Observations	
b. Design and Construction Data	
c. Operating Records	
d. Post Construction Changes	
e. Seismic Stability	

## SECTION 7: ASSESSMENT, RECOMMENDATIONS & REMEDIAL MEASURES

7.1 <u>Dam Assessment.....</u>	16
a. Condition	
b. Adequacy of Information	
c. Urgency	
d. Need for Additional Information	
7.2 <u>Recommendations.....</u>	16
7.3 <u>Remedial Measures.....</u>	17
a. Operation and Maintenance Procedures	
7.4 <u>Alternatives.....</u>	17

## APPENDICES

	<u>Page No.</u>
Appendix A: <u>Inspection Checklist</u>	A-1 to A-5
Appendix B: <u>Engineering Data and Correspondence</u>	
Dam Plan, Profile and Sections	Sheet B-1
List of Existing Plans	B-1
Summary of Data and Correspondence	B-2
Data and Correspondence	B-3 to B-6
Appendix C: <u>Detail Photographs</u>	
Location Plan of Photographs	Sheet C-1
Photographs	C-1 to C-2
Appendix D: <u>Hydraulic/Hydrologic Computations</u>	
Drainage Area Map	Sheet D-1
Computations	D-1 to D-16
Preliminary Guidance	i - viii
Appendix E: <u>Information as Contained in the National Inventory of Dams</u>	E-1





OVERVIEW PHOTO

US ARMY ENGINEER DIV. NEW ENGLAND CORPS OF ENGINEERS WALTHAM, MASS.		NATIONAL PROGRAM OF INSPECTION OF NON-FED DAMS		MALTBY LAKE #1 DAM		WEST HAVEN		DATE March '79	
CAHN ENGINEERS INC. WALLINGFORD, CONN. ENGINEER				TR - WEST RIVER		CONNECTICUT		CE # 27 660 KA	
								PAGE viii	



# LOCATION MAP CONNECTICUT



## PHASE I INSPECTION REPORT

### MALTBY LAKE DAM NO. 1

#### SECTION I - PROJECT INFORMATION

##### 1.1 GENERAL

a. Authority - Public Law 92-367, August 8, 1972, authorized the Secretary of the Army, through the Corps of Engineers, to initiate a National Program of Dam Inspection throughout the United States. The New England Division of the Corps of Engineers has been assigned the responsibility of supervising the inspection of dams within the New England Region. Cahn Engineers, Inc. has been retained by the New England Division to inspect and report on selected dams in the State of Connecticut. Authorization and notice to proceed were issued to Cahn Engineers, Inc. under a letter of March 30, 1979 from John P. Chandler, Colonel, Corps of Engineers. Contract No. DACW 33-79-3-0059 has been assigned by the Corps of Engineers for this work.

b. Purpose of Inspection Program - The purposes of the program are to:

1. Perform technical inspection and evaluation of non-federal dams to identify conditions requiring correction in a timely manner by non-federal interests.
2. Encourage and prepare the States to quickly initiate effective dam inspection programs for non-federal dams.
3. To update, verify and complete the National Inventory of Dams.

c. Scope of Inspection Program - The scope of this Phase I inspection report includes:

1. Gathering, reviewing and presenting all available data as can be obtained from the owners, previous owners, the state and other associated parties.
2. A field inspection of the facility detailing the visual condition of the dam, embankments and appurtenant structures.
3. Computations concerning the hydraulics and hydrology of the facility and its relationship to the calculated flood through the existing spillway.



4. An assessment of the condition of the facility and corrective measures required.

It should be noted that this report does not pass judgment on the safety or stability of the dam other than on a visual basis. The inspection is to identify those features of the dam which need corrective action and/or further study.

## 1.2 DESCRIPTION OF THE PROJECT

a. Location - The dam is located on a tributary to the West River (referred to as Silver Brook on Connecticut state highway plans) in an urban area of the Town of West Haven, County of New Haven, State of Connecticut. The dam is shown on the U.S.G.S. New Haven Quadrangle Map as having coordinates latitude N 41° 18.3' and longitude W 72° 58.3'.

b. Description of Dam and Appurtenances - The 182 foot long dam consists of two main sections. The upstream part is an earthfill dam built in 1862 which has a slope of approximately 1.5 horizontal to 1 vertical with riprap on its face. The downstream part, built in 1900, is a sandstone masonry gravity section with an 8 foot wide top and 20 foot wide bottom. The upstream face of the masonry section is vertical, and was covered with cement mortar and two coats of Portland cement grout. The downstream face of the masonry section has an inclination of 1 horizontal to 3 vertical. The space between the two sections was filled with a well compacted clayey earth. The dam is founded on bedrock and has a length of 182 feet from the left abutment to the right edge of the spillway wall. The dam has a height of 26+ feet and a top width of 26 to 36 feet. The water level in the lake is maintained by flow from the upper Maltby lakes, which in turn are supplied from the Wepawaug Reservoir, via the Wepawaug Tunnel which flows to Maltby Lake No. 3.

The spillway is a 21.5 foot long stone masonry structure at the right side of the dam. It has a rectangular broad-crested weir with 4 feet of freeboard between its crest and the top of the dam. The spillway bridge has 2.8 feet of clearance from the top of the weir. The spillway discharge channel is a 10 foot wide, 3 foot deep trough with concrete walls having a stone coping. The channel leads to a 10'x5.1' concrete arch culvert which runs under Route 34, immediately downstream of the dam.

The outlets, near the center of the dam, consist of a 16 inch supply main with an intake structure at the upstream toe housing two 12 inch inlets with removable screens. The supply is gated at a downstream gate house, from which water is directed to treatment facilities. Approximately 15 feet to the right of the 16 inch pipe is a 10 inch low level outlet with a gate accessible through a manhole approximately 25 feet from the downstream toe. The 10 inch conduit discharges into the same conduit which carries the spillway discharge. In addition, there is a 20 inch pipe which directs water from the upper Maltby Lakes, under the dam to the downstream gate house. The operator stated that all gates are operable.

c. Size Classification - SMALL - The dam impounds 260 acre-feet of water with the reservoir level at the top of the dam, which at elevation 137.3 MSL is 26 feet above the old streambed. According to the Recommended Guidelines, this dam is classified as small in size.

d. Hazard Classification - HIGH - The dam is located immediately upstream of Connecticut Route 34 and an urbanized commercial and residential section of West Haven near Morris Avenue, Hillside Street, Winfred Street, and Forest Hills Road, which would be in the path of a breach outflow.

e. Ownership - New Haven Water Co.  
90 Sargent Drive  
New Haven, Ct. 06511  
Mr. Jack Reynolds (203) 624-6671

f. Operator - Mr. Carl Benkson  
New Haven Water Co.  
(203) 387-3930

g. Purpose of Dam - Public water supply.

h. Design and Construction History - The following information is believed to be accurate based on the plans and correspondence available. The original earth dam was built in 1862 and was acquired in 1876 by the New Haven Water Company with the purchase of the Fair Haven Water Company. The masonry section was built in 1900 by the New Haven Water Company, as engineered by Albert B. Hill and constructed by Charles W. Blakeslee and Sons. The discharge culvert under Route 34 was built in 1932 or shortly thereafter, at which time the stone coping was added to the spillway channel walls.

i. Normal Operational Procedures - The gate on the 16 inch supply pipe is operated as needed for water supply purposes. The low level outlet is opened for several hours at least once each year for flushing. Lake level readings are taken daily.

### 1.3 PERTINENT DATA

a. Drainage Area - 1.3 square miles of rolling, wooded terrain with some residential development.

b. Discharge at Damsite - Discharge is through a 16 inch supply main and a 10 inch low level outlet.

- |   |   |
|---|---|
| 1. Outlet Works (conduits):   | 16 inch supply main<br>@ invert el. 118.3 <sub>±</sub>              |
|   | 10 inch low level<br>outlet @ el. 118 <sub>±</sub>                  |
| 2. Max. known flood @<br>damsite:                                     | Unknown   |
| 3. Ungated spillway capacity<br>@ top of dam el. 137.3:               | 520 cfs. (does not<br>includes swale over-<br>flow)                 |
| 4. Ungated spillway capacity<br>@ test flood el.:                     | N/A   |
| 5. Gated spillway capacity @<br>normal pool el.:                      | N/A   |
| 6. Gated spillway capacity @<br>test flood el.:                       | N/A   |
| 7. Total spillway capacity @<br>test flood el.:                       | N/A   |
| 8. Total project discharge @<br>test flood el. 137.9:                 | 1220 cfs.   |
| c. <u>Elevations</u> (Feet Above Mean Sea Level = El. MHW +<br>3.33') |   |
| 1. Streambed at centerline of dam:                                    | 111.3 <sub>±</sub>  |
| 2. Maximum tailwater:   | N/A   |
| 3. Upstream portal invert<br>diversion tunnel:                        | 165 <sup>+</sup> (Invert of dis-<br>charge to Maltby Lake<br>No. 3) |
| 4. Recreation pool:   | N/A   |
| 5. Full flood control pool:   | N/A   |

- |  |       |
|--|-------|
| 6. Spillway crest:                     | 133.3 |
| El. of lowest swale:                   | 136.4 |
| 7. Design surcharge (original design): | N/A   |
| 8. Top of dam:                         | 137.3 |
| 9. Test flood design surcharge:        | 137.9 |
- d. Reservoir
- |                                  |                    |
|----------------------------------|--------------------|
| 1. Length of maximum pool:       | 2200 ft. (Approx.) |
| 2. Length of recreation pool:    | N/A                |
| 3. Length of flood control pool: | N/A                |
- e. Storage
- |                         |               |
|-------------------------|---------------|
| 1. Recreation pool:     | N/A           |
| 2. Flood control pool:  | N/A           |
| 3. Spillway crest pool: | 161 acre-ft.  |
| 4. Top of dam:          | 260 acre-ft.  |
| 5. Test flood pool:     | 275± acre-ft. |
- f. Reservoir Surface
- |                        |            |
|------------------------|------------|
| 1. Recreation pool:    | N/A        |
| 2. Flood control pool: | N/A        |
| 3. Spillway crest:     | 22.9 acres |
| 4. Test flood pool:    | 25+ acres  |
| 5. Top of dam:         | 25 acres   |
- g. Dam
- |            |   |
|------------|---|
| 1. Type:   | Earthfill with downstream masonry gravity section |
| 2. Length: | 182' (left abutment to right spillway wall)       |

- |                     |   |
|---------------------|---|
| 3. Height:          | 26 <sup>±</sup> ft.   |
| 4. Top width:       | 26 to 36 ft. (Approx)   |
| 5. Side slopes:     | 1.5 H to 1 V (Upstream)<br>1 H to 3 V (Downstream)                                      |
| 6. Zoning:          | Clayey material<br>placed between<br>upstream earth and<br>downstream stone<br>sections |
| 7. Impervious core: | N/A   |
| 8. Cutoff:          | N/A   |
| 9. Grout curtain:   | N/A   |
| 10. Other:          | N/A   |
- h. Diversion and Regulating Tunnel - N/A
- i. Spillway
- |                        |   |
|------------------------|---|
| 1. Type:               | Broad-crested rectangular<br>masonry weir                     |
| 2. Length of weir:     | 21.5 ft.  |
| 3. Crest elevation:    | 133.3   |
| 4. Gates:              | None  |
| 5. Upstream channel:   | 4H to 1V  |
| 6. Downstream channel: | 10'x3' discharge<br>channel to culvert<br>under Conn. Rte. 34 |
| 7. General:            | N/A   |
- j. Regulating Outlets
- |            |                               |
|------------|-------------------------------|
| 1. Invert: | 118.3 <sub>±</sub>            |
| 2. Size:   | 16" and 10" diameter<br>pipes |

3. Description:

16" supply main  
10" low level outlet

4. Control Mechanism:

Valve at downstream  
gatehouse (16" pipe)  
and valve at downstream  
manhole near toe (10" pipe)

5. Other:

20" pipe under dam  
to downstream gate-  
house from upper  
Maltby Lakes



## SECTION 2: ENGINEERING DATA

### 2.1 DESIGN

a. Available Data - The available data consists of drawings and records by the State of Connecticut D.E.P., Albert B. Hill, Blair and Marchant, and the New Haven Water Co. (See Appendix B)

b. Design Features - The drawings and records indicate the design features stated previously herein.

c. Design Data - There were no engineering values, assumptions, test results, or calculations available for the 1862 construction of the earth dam or the 1900 construction of the masonry section.

### 2.2 CONSTRUCTION

a. Available Data - Descriptions are available of the procedure used to build the downstream stone section while incorporating the upstream earth section into the dam. (See Appendix B) No other construction data was obtained.

b. Construction Considerations - As-built drawings are not available.

### 2.3 OPERATIONS

Lake level readings are taken daily. To our knowledge, the dam spillway capacity has never been exceeded. No other formal operation records are known to exist.

### 2.4 EVALUATION

a. Availability - Existing data was provided by the Owner and by the State of Connecticut D.E.P. The owner made the facility available for visual inspection.

b. Adequacy - The limited amount of detailed engineering data available was generally inadequate to perform an in-depth assessment of the dam, therefore, the final assessment of this dam must be based primarily on visual inspection, performance history, hydraulic computations and approximate hydrologic judgements.

c. Validity - A comparison of records data and visual observation reveals that the as-built condition of the dam differs from that portrayed on the existing plans of the dam by Albert B. Hill. The major difference appears to be in the configuration of the spillway and the fact that it is 21.5 feet long, rather than 30 feet long as portrayed on the existing plans.

## SECTION 3: VISUAL INSPECTION

### 3.1 Findings

a. General - The general condition of the dam is good. Inspection did reveal some areas requiring attention. The reservoir level was at elevation 133.4 at the time of our inspection, and the weather was sunny, warm and dry.

b. Dam Crest - The crest of the dam has a grass cover with a service road along its center line (Photo 1). The downstream portion of the crest is an 8 foot wide stone masonry section (Photo 2). No misalignment, depressions or cracks were observed along the dam crest. There was a low swale area on the natural ridge approximately 265 feet to the right of the spillway, which at elevation 136.4, would allow water from the reservoir to overflow 0.9 feet before the lake level reaches the top of the dam.

Upstream Slope - The upstream slope has an inclination of 1.5 horizontal to 1 vertical and is covered with hand placed riprap. No significant loss of riprap or instability was noted during the inspection.

Downstream Slope - The downstream slope of the dam is the rubble masonry gravity section with a downstream face inclination of 1 horizontal to 3 vertical. The vertical upstream face of the masonry section was covered with a cement mortar coating and then had two coats of Portland cement grout brushed on when constructed. The downstream masonry face of the dam has some minor cracks along masonry joints with evidence of lime efflorescence (Photo 2). Some vines were observed on the lower portion of the slope. There are areas of runoff erosion along the toe of the left abutment where there is no erosion protection (Photo 2). The downstream slope of the earth embankment to the right of the spillway is steep and covered with wood chips for erosion protection (Photo 3). It was not apparent whether this area was a portion of the dam, and it showed no signs of erosion or instability.

Spillway - The 21.5 foot long spillway is a stone masonry broad-crested rectangular weir with 4 feet of freeboard between its crest and the top of the dam. The spillway is spanned by a bridge which has a 2.8 foot high clearance from the top of the weir (Photo 3). The spillway is generally in good condition. Some minor deterioration was observed on the downstream wingwalls. The dam operator said there are several seepage spots on the spillway face which can be seen during the dry season. Some leakage at the spillway base was noted also by maintenance personnel in May, 1964 according to existing correspondence. During a preliminary inspection performed on April 17, 1979, at a time when water was not flowing over the spillway, we observed seepage in two

places immediately adjacent downstream of the weir. Seepage was emanating from the right training wall at the bedrock interface, and on the left training wall from the mortar joints between two stone blocks. Seepage flow observed was minor, but steady.

c. Appurtenant Structures - The concrete chamber of the upper gatehouse has no signs of visible cracks or spalling (Photo 1). No substantial rusting was observed on the metal service bridge.

The spillway discharge channel is a 10 foot wide and 3 foot deep open trough with concrete stone coping walls, and leads to a concrete arch culvert under Connecticut Route 34 immediately downstream. Some cracking and spalling of the concrete was observed at the left wall of the channel (Photo 4).

d. Reservoir Area - The reservoir area is bordered on the southeast by Route No. 34, with the exception of a small portion of the lake about 1/2 mile west along Route 34 from the dam. This small portion is on the south side of Route 34 and is joined to the main portion of Maltby Lake No. 1 by a conduit through the roadway embankment. The area directly surrounding the reservoir is wooded and predominantly undeveloped.

e. Downstream Channel - The downstream channel is the natural streambed on the other (southeast) side of Route 34 which flows for a short distance through an urban area of West Haven before being carried within the storm drainage system of West Haven.

The Route 34 roadway immediately downstream of the dam is at the same approximate elevation as the top of the upstream headwall for the spillway discharge conduit under the road. Therefore, when spillway flow exceeds the conduit capacity, water will flow over the roadway with no significant attenuating affect due to the roadway itself.

### 3.2 Evaluation

Based upon the visual inspection, it was possible to assess the dam as being generally in good condition. The following features which could influence the future condition and/or stability of the dam were identified.

1. The deteriorated masonry and concrete surfaces of the spillway and the spillway discharge channel should be repaired to prevent their further deterioration.

2. The seepage from the spillway face and spillway channel walls should be monitored periodically for any change in the condition.
3. Vegetation, such as vines, at the downstream slope of the masonry section should be removed to avoid deterioration of the masonry.
4. Surface erosion along the downstream face of the left abutment should be repaired to prevent further, more serious erosion.
5. With the low level outlet pipes gated on the downstream side of the dam, the conduits through the dam are under constant head. This situation is not desirable, and in the future should repair or redesign of the hydraulic facilities take place, consideration should be given to the installation of gates on the upstream side of the dam.



## SECTION 4: OPERATIONAL PROCEDURES

### 4.1 Regulating procedures

Operating procedures consist of regulating the flow through the 16 inch main supply line as necessary for water supply purposes. The low level outlet is opened for several hours once per year for flushing. The level of all three Maltby Lakes is maintained by regulating flow into Maltby Lake No. 3 via the Wepawaug Tunnel, from Wepawaug Reservoir. Lake level readings are taken daily.

### 4.2 Maintenance of the Dam

Grass on and around the dam is cut regularly. Debris is removed from the spillway channel and intake screens are cleaned as needed.

Three years ago the New Haven Water Company instituted a yearly program of inspection of all their dams including Maltby Lake Dam No. 1, by a consultant competent in the field of dam inspections.

### 4.3 Maintenance of Operating Facilities

Gate operating mechanisms are maintained on an as-needed basis. The low level outlet is opened once per year for several hours for flushing.

### 4.4 Description of any Formal Warning System in Effect

No formal warning system is in effect. The operator reports any emergencies to his supervisor.

### 4.5 Evaluation

The operation and maintenance procedures are generally good; however, there are some areas requiring improvement. A formal program of operations and maintenance procedures should be implemented, including documentation to provide complete records for future reference. Also, a formal warning system should be developed and implemented within the time frame indicated in Section 7.1c. Remedial operations and maintenance recommendations are presented in Section 7.

## SECTION 5: HYDRAULIC/HYDROLOGIC

### 5.1 Evaluation of Features

a. General - The Maltby Lake No. 1 watershed includes the drainage areas of Maltby Lakes No. 2 and 3 located immediately upstream, and the tunnel diversion to Maltby Lake No. 3 from Wepawaug and Trout Brooks. As reported by the New Haven Water Company, the diversion from Wepawaug Reservoir is gated at the tunnel inlet. The diversion from Trout Brook is gated at its junction with the Wepawaug Tunnel. As both diversions are controlled and could be closed to Maltby Lake No. 3 as part of the emergency operational procedures, flow from these diversions will not be considered in our hydraulic/hydrologic analysis of Maltby Lake Dam No. 1.

The peak inflow to Maltby Lake No. 1 is regulated by Maltby Lake Dams No. 2 and 3. Approximate routing of the Probable Maximum Flood (PMF) and the 1/2 PMF peak inflows has demonstrated that the regulating effect on the peak inflow of the two upstream Maltby Lakes is relatively small and, therefore, it will not be considered in the analysis.

The terrain to the right of the dam rises and falls along a natural ridge forming a series of swales, one of which, located 265 feet to the right of the spillway, may be low enough to allow water from the reservoir to overflow at an elevation up to 0.9 feet below the top of the dam elevation (See Appendix D-7). Spillway capacity for this dam was determined both with and without overflow through the swale; the case considered appropriate for this dam will not include overflow from the swale, as it is a condition which should be corrected.

b. Design Data - No hydraulic/hydrologic design data could be found for the original dam construction in 1862 or for the construction of the dam to its present configuration in 1900.

c. Experience Data - No information on serious problem situations arising at the dam was found, and it does not appear the dam has been overtopped.

d. Visual Observations - The wooden bridge spanning the spillway is supported by four steel beams which are approximately 2.8 feet above the spillway crest, and 1.2 feet below the top of the dam. During heavy flows approaching the top of the dam, the low bridge beams could retain large floating debris and cause an obstruction of the spillway.



The bar screen over the entrance to the spillway discharge culvert immediately downstream of the dam also could easily retain debris and obstruct the flow to the culvert. While this would back up flow at the toe of the dam, its effect on the stability of the dam or the flow over the spillway would be negligible.

e. Test Flood Analysis - The test flood for this high hazard, small size dam is equivalent to the Probable Maximum Flood (PMF). Based upon "Preliminary Guidance for Estimating Maximum Probable Discharge," dated March, 1978, peak inflow to the reservoir is 1450 cfs (Appendix D-5); peak outflow is 1220 cfs with the dam overtopped 0.6 feet (Appendix D-13). Based upon our hydraulic computations, the spillway capacity is 520 cfs (not including overflow from a natural swale about 265 feet to the right of the spillway) which is approximately 43% of the routed Test Flood outflow. The spillway capacity including the swale overflow would be 590 cfs, or approximately 48% of the routed Test Flood outflow.

f. Dam Failure Analysis - Utilizing the April 1978 "Rule of Thumb Guidance for Estimating Downstream Dam Failure Hydrographs", the peak failure outflow from the dam breaching would be 14,100 cfs. A breach of the dam would result in a flood depth of 11 feet immediately downstream of the dam which would submerge the adjacent portion of Route 34, and a flood depth outside the stream channel of 4 feet above the ground at the initial impact area (See Appendix D-16), which is an urbanized section of West Haven near Morris Avenue, Hillside Street, Winfred Street, and Forest Hills Road.

## SECTION 6: STRUCTURAL STABILITY

### 6.1 Evaluation of Structural Stability

a. Visual Observation - The visual inspection did not reveal any indications of stability problems. There are some areas of cracking, spalling and seepage at the gravity masonry section of the dam spillway and spillway discharge channel, as described in Section 3, however they are not considered stability concerns.

b. Design and Construction Data - The limited amount of design and construction data is not sufficient to permit an in-depth analysis of the stability of the dam.

c. Operating Records - The operating records do not include any indication of dam instability since its construction in 1900 or since subsequent modifications have been performed.

d. Post-Construction Changes - There are no records available concerning the post-construction changes of the dam. However, there are two drawings showing that the stone coping of the spillway channel walls and modification of the culvert under the Route 34 were implemented in 1932. These changes have no effect on the stability of the dam.

e. Seismic Stability - The dam is in Seismic Zone 1 and according to the Recommended Guidelines, need not be evaluated for seismic stability.

## SECTION 7: ASSESSMENT, RECOMMENDATIONS AND REMEDIAL MEASURES

### 7.1 Dam Assessment

a. Condition - Based upon the visual inspection of the site and its past performance, the dam appears to be in good condition. No evidence of structural instability was observed in the dam and its appurtenances. The embankment is generally in good condition. There are some areas requiring attention, such as project discharge capacity and maintenance items.

Based upon "Preliminary Guidance for Estimating Maximum Probable Discharge" dated March, 1978, peak inflow to the reservoir is 1450 cubic feet per second; peak outflow is 1220 cubic feet per second with the dam overtopped 0.6 feet. Based upon our hydraulics computations, the spillway capacity is 520 cubic feet per second, (not including the swale overflow) which is equivalent to approximately 43% of the routed Test Flood outflow.

b. Adequacy of Information - The information available is such that an assessment of the condition and stability of the dam must be based solely on visual inspection, past performance of the dam, and sound engineering judgement.

c. Urgency - It is recommended that the measures presented in Section 7.2 and 7.3 be implemented with two years of the owner's receipt of this report.

d. Need for Additional Information - There is a need for more information as recommended in Section 7.2.

### 7.2 Recommendations

1. Based upon the computations in Appendix D, the dam spillway capacity will be exceeded by the Test Flood. More sophisticated flood routing should be undertaken by hydrologists/hydraulics engineers to refine the spillway design flood figures. A study should be undertaken to determine the spillway capacity and potential for overtopping. Recommendations should be made by the engineer and implemented by the owner to increase the project discharge capacity based upon the refined spillway design flood figures.

2. A registered professional engineer qualified in dam design should develop recommendations to raise the elevation of the swale, located 265 feet to the right of the spillway to the elevation of the top of the dam. This would prevent flow from the swale under high water conditions, which would cross Route 34 and cause flooding in the urbanized area of West Haven immediately downstream.

### 7.3 Remedial Measures

a. Operation and Maintenance Procedures - The following measures should be undertaken within the time frame indicated in Section 7.1c, and continued on a regular basis.

1. Round-the-clock surveillance should be provided by the owner during periods of unusually heavy precipitation. The owner should develop a formal warning system with local officials for alerting downstream residents in case of an emergency.

2. A formal program of operation and maintenance procedures should be instituted and fully documented to provide accurate records for future reference.

3. The New Haven Water Company has instituted a yearly program of technical inspection of all their dams, including Maltby Lake No. 1, by a consultant competent in the field of dam inspection. This program, in effect for 3 years, should be continued and should include the operation of the low level outlet works.

4. The cracking and spalling of the concrete and masonry of the gravity section of the dam, the downstream face of the spillway and the spillway diversion channel walls should be repaired.

5. Any seepage on the downstream face or training walls of the spillway and its channel walls should be monitored periodically.

6. The cutting of grass on the crest and the toe of the dam should be continued as part of the routine dam maintenance. Any vegetation on the downstream face of the masonry section of the dam should be removed.

7. Erosion of the downstream face of the left abutment should be repaired, and the appropriate measures taken to prevent further erosion.

8. The diversions into Maltby Lake No. 3 from Wepawaug Reservoir and Trout Brook should be closed during major storms as part of the emergency operating procedures for the Maltby Lake Dams.

### 7.4 Alternatives

This study has identified no practical alternatives to the above recommendations.

APPENDIX A

INSPECTION CHECKLIST



VISUAL INSPECTION CHECK LIST  
PARTY ORGANIZATION

PROJECT MALTBY LAKE DAM No.1

DATE: MAY 1, 1978

TIME: \_\_\_\_\_

WEATHER: SUNNY, 70°

W.S. ELEV. \_\_\_\_\_ U.S. — DN.S

PARTY:

INITIALS:

DISCIPLINE:

1. <u>PETER M. HEYNEN</u>	<u>PMH</u>	<u>CAHN ENGINEERS, INC.</u>
2. <u>CALVIN R. GOLDSMITH</u>	<u>CRG</u>	" " "
3. <u>MIRON PETROVSKY</u>	<u>MP</u>	" " "
4. <u>GEORGE STEPHENS</u>	<u>GS</u>	" " "
5. <u>CARL BENGSTON</u>	<u>CB</u>	<u>NEW HAVEN WATER CO.</u>
6. _____	_____	_____

PROJECT FEATURE

INSPECTED BY

REMARKS

1. <u>EARTH DAM EMBANKMENT</u>	<u>PMH, CRG, MP, GS, CB</u>	
2. <u>SPILLWAY AND CHANNELS</u>	" " " " "	
3. <u>UPPER AND LOWER GATE HOUSES</u>	" " " " "	
4. <u>METAL SERVICE BRIDGE</u>	" " " " "	
5. _____		
6. _____		
7. _____		
8. _____		
9. _____		
10. _____		
11. _____		
12. _____		

## PERIODIC INSPECTION CHECK LIST

Page A-2PROJECT MALTBY LAKE DAM No.1DATE MAY 1, 1979PROJECT FEATURE EARTHFILL DAM WITH DOWNSTREAM BY PMH, CRG, MPGS, CB  
MASONRY GRAVITY SECTION

AREA EVALUATED	CONDITION
<u>DAM EMBANKMENT</u>	
Crest Elevation	137.3 ±
Current Pool Elevation	
Maximum Impoundment to Date	N/A
Surface Cracks	NONE OBSERVED
Pavement Condition	N/A
Movement or Settlement of Crest	NONE OBSERVED
Lateral Movement	NONE OBSERVED
Vertical Alignment	NONE OBSERVED
Horizontal Alignment	NONE OBSERVED
Condition at Abutment and at Concrete Structures	GOOD
Indications of Movement of Structural Items on Slopes	NONE OBSERVED
Trespassing on Slopes	NONE
Sloughing or Erosion of Slopes or Abutments	NONE OBSERVED
Rock Slope Protection-Riprap Failures	NONE OBSERVED
Unusual Movement or Cracking at or Near Toes	NONE OBSERVED
Unusual Embankment or Downstream Seepage	NONE OBSERVED
Piping or Boils	NONE OBSERVED
Foundation Drainage Features	N/A
Toe Drains	N/A
Instrumentation System	N/A

## PERIODIC INSPECTION CHECK LIST

Page A-3PROJECT MALBY LAKE DAM No. 1DATE MAY 1, 1979PROJECT FEATURE UPPER GATEHOUSEBY PMH, CRG, MP, GS, CD

AREA EVALUATED	CONDITION
<u>OUTLET WORKS-CONTROL TOWER</u>	<u>BRICK STRUCTURE ON CONCRETE CHAMBER</u>
a) <u>Concrete and Structural</u>	
General Condition	GOOD
Condition of Joints	NONE OBSERVED
Spalling	NONE OBSERVED
Visible Reinforcing	NONE OBSERVED
Rusting or Staining of Concrete	NONE OBSERVED
Any Seepage or Efflorescence	NONE OBSERVED
Joint Alignment	NONE OBSERVED
Unusual Seepage or Leaks in Gate Chamber	NOT OBSERVED
Cracks	NONE OBSERVED
Rusting or Corrosion of Steel	NOT OBSERVED
b) <u>Mechanical and Electrical</u>	NOT OBSERVED
Air Vents	
Float Wells	
Crane Hoist	
Elevator	
Hydraulic System	
Service Gates	
Emergency Gates	
Lightning Protection System	
Emergency Power System	
Wiring and Lighting System	

## PERIODIC INSPECTION CHECK LIST

Page A-4PROJECT MALBY LAKE DAM No.1DATE MAY 1, 1979PROJECT FEATURE LOW LEVEL PIPESBY PMH, CRG, MP, GS, CB

AREA EVALUATED	CONDITION
<u>OUTLET WORKS-TRANSITION AND CONDUIT</u>  General Condition of Concrete Rust or Staining on Concrete Spalling Erosion or Cavitation Cracking Alignment of Monoliths Alignment of Joints Numbering of Monoliths	Two 16" and 10" DIAMETER METAL PIPES THROUGH DAM. NOT ABLE TO OBSERVE CONDUITS, HOWEVER, THE OPERATOR SAID THAT ALL CONDUITS ARE OPER- ABLE BY GATES AT D/S GATEHOUSE (16" PIPE) AND TOE MANHOLE (10" PIPE)

## PERIODIC INSPECTION CHECK LIST


Page A-5PROJECT MALBY LAKE DAM No. 1DATE MAY 1, 1979PROJECT FEATURE SPILLWAY AND CHANNELSBY PMH, CRG, MP, GS, CB


AREA EVALUATED	CONDITION
<u>OUTLET WORKS-SPILLWAY WEIR, APPROACH AND DISCHARGE CHANNELS</u>	
a) <u>Approach Channel</u>	STONE MASONRY CHANNEL
General Condition	GOOD
Loose Rock Overhanging Channel	NONE
Trees Overhanging Channel	NONE
Floor of Approach Channel	NOT OBSERVED (UNDER WATER)
b) <u>Weir and Training Walls</u>	STONE MASONRY SPILLWAY
General Condition of Concrete	GOOD
Rust or Staining	NOT OBSERVED
Spalling	MINOR DISTRESSES OF TRAINING WALLS
Any Visible Reinforcing	NONE
Any Seepage of Efflorescence	MINOR SEEPAGE FROM RIGHT TRAINING WALL AT BEDROCK INTERFACE
Drain Holes	N/A
c) <u>Discharge Channel</u>	CONCRETE WALL TRAY
General Condition	GOOD, SOME SPALLING AT LEFT WALL
Loose Rock Overhanging Channel	NONE
Trees Overhanging Channel	NONE
Floor of Channel	GOOD, HAND PLACED STONE
Other Obstructions	NONE




APPENDIX B

ENGINEERING DATA AND CORRESPONDENCE





SECTION B-B



3 THIS PLAN WAS COMPILED FROM EXISTING PLANS ENTITLED "PLAN FOR REBUILDING MALTBY DAM NO. 1" BY ALBERT HILL, CULVERT FOR SPILLWAY CHANNEL MALTBY LAKE NO. 1 BY BLAIR & MARCHANT DATED MARCH 1932, TWO UNTITLED AND UNDATED PLANS AND FROM ROUGH FIELD MEASUREMENTS. DIMENSIONS SHOWN ARE APPROXIMATE AND NOT ALL STRUCTURAL AND/OR TOPOGRAPHIC FEATURES ARE IDENTIFIED.

2 ELEVATIONS SHOWN ARE BASED ON THE MEAN SEA LEVEL DATUM. ELEVATIONS SHOWN WERE CONVERTED FROM THE MEAN HIGH WATER DATUM SHOWN ON THE ORIGINAL PLANS, WHICH IS APPROXIMATELY 3.3 FEET ABOVE THE MEAN SEA LEVEL DATUM.

LEFT NATURAL  
GROUND ABUTMENT

CAHN ENGINEERS INC  
WALLINGFORD, CONNECTICUT  
ENGINEER

U.S. ARMY ENGINEER DIV. NEW ENGLAND  
CORPS OF ENGINEERS  
WALTHAM, MASS.

NATIONAL PROGRAM OF INSPECTION OF NON-FED. DAMS

PLAN, ELEVATION AND SECTION  
MALTBY LAKE DAM No. 1

TR - WEST RIVER

WEST HAVEN, CONNECTICUT

DRAWN BY	CHECKED BY	APPROVED BY	SCALE AS NOTED
P. N.	SPC	P. H.	DATE JUNE 1979 SHEET B-1

# LIST OF EXISTING PLANS

"New Haven Water Co., Plan for Rebuilding Maltby No. 1 Dam."  
Albert B. Hill, Consulting Engineer  
1901

"New Haven Water Co., Culvert for Spillway Channel, Maltby  
Lake No. 1."  
Blair and Marchant, Inc.  
March, 1932

"New Haven Water Co. Spillway Channel - Maltby Lake No.  
1, Plan of Sandstone Coping"  
Blair and Marchant, Inc.  
June, 1932

"New Haven Water Co., Contour Map, Area North of Maltby  
Lake No. 1"  
April, 1941, rev. March, 1946

# SUMMARY OF DATA AND CORRESPONDENCE

<u>DATE</u>	<u>TO</u>	<u>FROM</u>	<u>SUBJECT</u>	<u>PAGE</u>
May 21, 1964	Files	Water Resources Commission Supervision of Dams	Inventory Data	B-3
Aug. 1974	Files	New Haven Water co.	Statistics on Dams	B-4
-	Files	New Haven Water co.	Storage curve for lake	B-6



No. 4451

WATER RESOURCES COMMISSION  
SUPERVISION OF DAMS  
INVENTORY DATA

Inventoried  
By WPS

Date 21 MAY 1964

Name of Dam or Pond SALTBY LAKE (LOWER)

Code No. WS 28 012

Nearest Street Location ROUTE 34

Town WEST HAVEN

U.S.G.S. Quad. NEW HAVEN

Name of Stream UNNAMED

Owner NEW HAVEN WATER COMPANY

Address 100 CROWN STREET

NEW HAVEN

Pond Purpose WATER SUPPLY 1350'

Dimensions of Pond: Width 400 FEET Length 2000 FEET Area 20 ACRES

Total length of Dam 135 FEET Length of Spillway 20 FEET

Location of Spillway SOUTH - WEST END OF DAM

Height of Pond Above Stream Bed 25 FEET

Height of Embankment Above Spillway 5 FEET

Type of Spillway Construction MASONRY

Type of Dike Construction MASONRY EARTH ON STREAM

Downstream Conditions CONVERT UNDER ROUTE 34

Summary of File Data

Remarks SOME LEAKAGE NOTED AT BASE OF SPILLWAY

Would Failure Cause Damage?

YES

Class B B-3

## NEW HAVEN WATER COMPANY

NAME OF DAM Maltby Dam No. 1

TYPE A gravity section, masonry dam of rubble masonry with cut stone facing with an upstream earth embankment and gate-house at toe of the embankment reached by a steel bridge. A cement mortar coating was placed on the upstream face of this masonry section. Two good coats of Portland cement grout were brushed on the mortar coating.

LOCATION In West Haven, Connecticut on the north side of Derby Avenue (State Highway No. 34) and approximately 3,200 feet east of the Orange-West Haven town line.

SUPPLY SYSTEM Maltby

DATE OF CONSTRUCTION

ORIGINAL 1900

OTHER This dam replaced a smaller, lower dam of earth built in 1862 which was acquired in 1876 by purchase of the Fair Haven Water Company. Somewhat upstream from the new masonry constructed in 1900, it was incorporated within the upstream embankment of the dam built in 1900 by N. H. Water Co. The space between the upstream face of the gravity masonry section and the downstream slope of this old 1862 earth dam was filled with "clayey earth, bonded into the old material, and thoroughly rammed."

ENGINEER

CONTRACTOR

1900 - Albert B. Hill

Charles W. Blakeslee &amp; Sons

	<u>Elevation</u>	<u>Length (Ft.)</u>	<u>Miscellaneous</u>
CREST	134 MHW	±240	Includes spillway
SPILLWAY	130 MHW	30	
AXIS OF B.-O.	115 MHW	Axis of lowest intake	
BED OF RIVER	±108 MHW	-	
DEEPEST FOUNDATION	±97 MHW	-	

DATE August 1974

## NEW HAVEN WATER COMPANY

Name of Dam Maltby Dam No. 1

HEIGHT FROM BED OF BROOK		26 feet
HEIGHT FROM DEEPEST FOUNDATION		37 feet
TOP WIDTH	Masonry section	8 feet
MAXIMUM WIDTH AT BOTTOM	Masonry section	20 feet
UPSTREAM SLOPE	Masonry section	Vertical
DOWNSTREAM SLOPE	Masonry section	4 Hor. on 12 Ver.
FREE BOARD - SPILLWAY TO CREST		4 feet

- SPILLWAY TO TOP OF COREWALL -

MISCELLANEOUS DATA    Masonry section founded on ledge rock. Studies and borings have been made for a proposed reservoir north of Route No. 34 (Derby Avenue) on Race Brook which would flow into the Wepawaug Tunnel which flows to the Maltby Lakes.

## WATERSHED TRIBUTARY TO:

	Wepawaug 7.8	
UPSTREAM DAMS	Trout Brook Div. 0.8=	8.6 Sq. Mi.
THIS DAM	Includes watersheds of Maltby No.2&3	1.2 Sq. Mi.
TOTAL WATERSHED TRIBUTARY TO THIS DAM		9.8 Sq. Mi.

RESERVOIR AREA AT FLOW LINE 22.9 Acres


RESERVOIR CAPACITY AT FLOW LINE -

RESERVOIR USABLE CAPACITY (To Lowest Outlet) 51 Mil. Gal.  
154,500 gal.

UPSTREAM DAMS    Wepawaug Dam; Trout Brook Diversion (these flow to Maltby Reservoir No. 3 via the Wepawaug Tunnel); Maltby Dam No. 2; and Maltby Dam No. 3.

DOWNSTREAM DAMS    None

# MALTBY LAKE #1



APPENDIX C

DETAIL PHOTOGRAPHS






PHOTO LOCATION PLAN

MALTBY LAKE DAM No.1  
SHEET C-1



PHOTO 1 - Upstream face of dam as seen from left abutment.  
Note intake structure and metal service bridge.



PHOTO 2 - Left abutment and downstream face of dam.  
Note efflorescence from stone block masonry.

US ARMY ENGINEER DIV. NEW ENGLAND  
CORPS OF ENGINEERS  
WALTHAM, MASS.

CAHN ENGINEERS INC.  
WALLINGFORD, CONN.  
ENGINEER

NATIONAL PROGRAM OF  
INSPECTION OF  
NON-FED. DAMS

Maltby Lake #1 Dam  
Tr - West River  
West Haven, Connecticut  
CE# 27 660 KA  
DATE May '79 PAGE C-1



PHOTO 3 - Right abutment and spillway crest.



PHOTO 4 - Entrance to culvert under road located near toe of dam. Note cracking and spalling of sides of concrete spillway channel.

US ARMY ENGINEER DIV. NEW ENGLAND  
CORPS OF ENGINEERS  
WALTHAM, MASS.

CAHN ENGINEERS INC.  
WALLINGFORD, CONN.  
ENGINEER


NATIONAL PROGRAM OF  
INSPECTION OF  
NON-FED. DAMS

Maltby Lake #1 Dam  
Tr. - West River  
West Haven, Connecticut  
CE# 27 660 KA  
DATE May '79 PAGE C-2

APPENDIX D  
HYDRAULICS/HYDROLOGIC COMPUTATIONS



USGS QUADRANGLE  
NEW HAVEN 1972





Project INSPECTION OF NON-FEDERAL DAMS IN NEW ENGLANDSheet D-1 of 16Computed By HLLChecked By CRGDate 6/9/79

Job Book Ref. \_\_\_\_\_

Other Refs. CE #27-660-KA

Revisions \_\_\_\_\_

HYDROLOGIC/HYDRAULIC INSPECTIONMALBY LAKE DAM #1, WEST HAVEN, CT.2) PERFORMANCE AT TEST FLOOD CONDITIONS1) MAXIMUM PROBABLE FLOODa) WATERSHED CLASSIFIED AS "ROLLING" TO "FLAT"b) WATERSHED AREA

THE MALBY LAKE #1 WATERSHED INCLUDES THE DRAINAGE AREAS OF MALBY LAKE #2 AND #3, WHICH ARE LOCATED JUST IMMEDIATELY  $\frac{1}{2}$  MI, AND THE TUNNEL DIVERSION TO MALBY LAKE #3 FROM THE WEPAWANG AND TROUT BROOKS.

THE DIVERSION FROM WEPAWANG RESERVOIR IS CONTROLLED\* (GATED) AT THE TUNNEL INLET AND THEREFORE IT CAN BE CLOSED TO MALBY #3 AS A PART OF THE OPERATIONAL PROCEDURES OF AN EMERGENCY WARNING SYSTEM. THEREFORE, FLOW FROM THIS CONTROLLED DIVERSION WILL NOT BE CONSIDERED IN THIS ANALYSIS.

THE DIVERSION FROM TROUT BROOK ALSO IS GATED AT ITS JUNCTION WITH THE WEPAWANG TUNNEL (N.H.W.C. DWG. NO. 90107, DATED JAN. 1959). THE OPERATIONAL CONDITION OF THE GATES IS UNKNOWN; IT WILL BE ASSUMED, HOWEVER, THAT THE DIVERSION CAN BE CONTROLLED AND THEREFORE, IT WILL NOT BE CONSIDERED IN THE ANALYSIS.

\*AS REPORTED BY THE NEW HAVEN WATER CO. TO C.E. (G. STEVENS) ON 6/4/79

Project NON-FEDERAL DAMS INSPECTION  
 Computed By HPD Checked By CRG  
 Old Book Ref. \_\_\_\_\_ Other Refs. CE #27-600 KA

Sheet D-2 of 16  
 Date 6/20/79  
 Revisions \_\_\_\_\_

### MALBY LAKE DAM #1

#### 1.0 - Cont'd) MAXIMUM PROBABLE FLOOD - WATERSHED AREA

MALBY LAKE #1 IS CROSSED BY THE STATE RTE #34 WHICH SEPARATES TWO RELATIVELY SMALL PORTIONS OF THE RESERVOIR TOWARDS THE RIGHT OF THE DAM (SOUTH-WEST END). THE INTERCONNECTION BETWEEN THE SEPARATED AND THE MAIN PORTION OF THE RESERVOIR UNDER THE HIGHWAY IS THROUGH 24" PIPE CULVERTS. THEREFORE, FLOW BETWEEN THESE SECTIONS IS RELATIVELY SMALL. FOR THE PURPOSE OF THESE ANALYSIS, THE HIGHWAY, A MAN MADE STRUCTURE, WILL NOT BE CONSIDERED AS REGULATING THE FLOW.

IT IS ALSO NOTED THAT A PARTIAL DIVERSION FROM A RELATIVELY FLAT SWAMPY AREA AT THE HEADWATERS OF THE COVE RIVER ALLOWS TO CERTAIN EXTENT BOTH INFLOW AND OUTFLOW TO AND FROM THE LAKE VIA THE LARGEST OF THE TWO PORTIONS SEPARATED BY RTE #34. BECAUSE OF THE EXPECTED NEGLECTIBLE CONTRIBUTION TO THE PMF FROM THIS DIVERSION, THE ADDITIONAL WATERSHED (UNDEFINED) WILL BE ASSUMED NON-EFFECTIVE.

FURTHER, THE POTENTIAL OF THIS CONNECTION AS AN AUXILIARY (EMERGENCY) OVERFLOW, ADDITIONAL SURCHARGE STORAGE CAPACITY, OR ANY OTHER EFFECT THAT THE SEPARATED PORTION OF THE RESERVOIR AND/OR DIVERSION MAY HAVE UPON THE PMF, SDF OR PEAK OUTFLOW AND SURCHARGE WILL NOT BE DIRECTLY CONSIDERED IN THE ANALYSIS. THE ONLY SIGNIFICANT EFFECT THAT RTE #34 MAY HAVE UPON THE SURCHARGE AND THAT WILL BE INCLUDED IN THE ANALYSIS IS IF OVERTOPPED. THIS OVERFLOW WHICH PRACTICALLY WILL NOT RETURN TO THE LAKE WILL BE ASSUMED TO DRAIN TO COVE RIVER.

Project NON-FEDERAL DAMS INSPECTION

Sheet D-3 of 16

Computed By WLL

Checked By CE

Date 6/20/79

Old Book Ref.

Other Refs. CE# 27-163-KA

Revisions

### MALBY LAKE DAM #1

#### 1.6-Cont'd) MAXIMUM PROBABLE FLOOD - WATERSHED AREA

(i) TOTAL \*D.A.  $\approx 1.29$  <sup>Sq. mi</sup> (4% WEPANAWG & TROUT BR. DIV. OF R.6 <sup>Sq. mi</sup>  
(UGGS HARTFORD & N.H.W.CO.)

(ii) D.A. 1/3 FROM MALBY LAKE #2: \*D.A.  $\approx 0.69$  <sup>Sq. mi</sup> (CE)

(iii) D.A. 1/3 FROM MALBY LAKE #3: \*D.A.  $\approx 0.31$  <sup>Sq. mi</sup> (CE)

(iv) DIRECT D.A. TO MALBY LAKE #1: \*D.A.  $\approx 0.29$  <sup>Sq. mi</sup> (SEE P. 2 OF THESE CURVES)

\*NOTE: DATA FROM U.S.G.S. HARTFORD OFFICE: DA-129 <sup>Sq. mi</sup>; CE CHECK MEASURE:  
(D.A.)<sub>TOT</sub>  $\approx 1.25$  <sup>Sq. mi</sup>; MALBY #1: (D.A.)<sub>1</sub>  $\approx 0.25$  <sup>Sq. mi</sup>; (D.A.)<sub>2</sub>  $\approx 0.31$  <sup>Sq. mi</sup>; (D.A.)<sub>3</sub>  $\approx 0.69$  <sup>Sq. mi</sup>;  
NEW HAVEN WATER CO. DATA SHEETS (INVENTORY) SHOWS (D.A.)<sub>TOT</sub>  $\approx 1.2$  <sup>Sq. mi</sup>  
(D.A.)<sub>3</sub>  $\approx 0.6$  <sup>Sq. mi</sup>; (D.A.)<sub>2</sub>  $\approx 0.35$  <sup>Sq. mi</sup>; (D.A.)<sub>1</sub>  $\approx 0.3$  <sup>Sq. mi</sup>.

C) FROM NED-ACE "PRELIMINARY GUIDANCE FOR ESTIMATING MAX. PROBABLE DISCHARGE": GUIDE CURVES FOR PMF - PEAK FLOW RATES EXTRAPOLATION TO D.A.'S  $\leq 2.0$  <sup>Sq. mi</sup>:

$$PMF \approx 2250 \text{ CFS/SQMI}$$

d) PEAK INFLOW:  $PMF \approx 2250 \times 1.29 = 2900$  <sup>CFS</sup> (TOTAL D.A.)

ACTUALLY, THE PEAK INFLOW TO MALBY DAM #1 IS REGULATED BY MALBY DAMS #2 & #3 WHICH DRAIN INTO IT. APPROXIMATE ROUTING OF THE PMF AND 1/2 PMF PEAK INFLOWS TO THESE RESERVOIRS HAS DEMONSTRATED THAT THE REDUCTION OF THE PEAK INFLOW TO MALBY LAKE #1 BECAUSE OF THE 1/2 RESERVOIRS REGULATION IS RELATIVELY SMALL (PMF RED. FROM 2900 <sup>CFS</sup> TO (1) 2550 <sup>CFS</sup> AND 1/2 PMF FROM 1450 <sup>CFS</sup> TO (1) 1130 <sup>CFS</sup>) AND THEREFORE, IT WILL NOT BE CONSIDERED IN THIS ANALYSIS.



Project NON-FEDERAL DAMS INSPECTION

Sheet 24 of 16

Prepared By Hill

Checked By CPG

Date 6/22/79

and Book Ref.

Other Refs. CE #27-610-KA

Revisions

### MALBY LAKE DAM #1

### 2) SPILLWAY DESIGN FLOOD (SDF)

#### a) CLASSIFICATION OF DAM ACCORDING TO NED-ACE RECOMMENDED GUIDELINES:

i) SIZE: STORAGE (MAX)  $\approx 260$  AC-FT (  $50 < S < 1000$  AC-FT )  
 HEIGHT  $\approx 26'$  (  $25 < H < 40$  FT )

STORAGE: FROM NEW HAVEN WATER CO. STORAGE VS. DEPTH BELOW SPILLWAY

AND ELEVATION CURVE: STORAGE TO SPILLWAY CREST  $S = 52.5$  AC-FT  $\approx 161$  AC-FT

ALSO, STORAGE TO LOWEST OUTLET FROM N.H.W. CO. DATA SHEET DATED AUG. 1979

USABLE STORAGE  $S_u = 51$  AC-FT. FROM SAME REFERENCE: LAKE AREA AT FLOOD

LINE:  $A = 22.9$  AC-FT. ASSUME AVE. AREA WITHIN EXPECTED SURCHARGE

$\bar{A} \approx 25$  AC-FT. SURCHARGE STORAGE FROM SPILLWAY CREST ELEV.  $133.3'$  MSL

( $130'$  MHW) TO TOP OF DAM ELEV.  $137.3'$  MSL ( $134'$  MHW):  $AS = 100$  AC-FT

$\therefore$  MAX. STORAGE:  $S_{MAX} \approx 160 + 100 \approx 260$  AC-FT. (SEE P. 2 OF THESE LOGS)

HEIGHT: FROM SAME DATA SOURCES AS FOR STORAGE. NATURAL STREAM

BED ELEV. (X)  $111.3'$  MSL ( $108'$  MHW).

(ii) HAZARD POTENTIAL: MALBY LAKE DAM #1 IS LOCATED IMMEDIATELY  $\frac{1}{2}$  MI FROM RTE #34 AND THE URBANIZED SECTION OF WEST HAVEN NEAR MORRIS AVE., HILLSIDE ST., WINFIELD ST. AND FOREST HILLS RD. WHICH WILL BE DIRECTLY AFFECTED UPON FAILURE OF THE DAM.

\*NOTE: ELEVATIONS GIVEN IN NEW HAVEN WATER CO. DATA ARE NEW HAVEN DATUM (MHW)

USGS DATUM (MSL)  $\approx$  NEW HAVEN DATUM (MHW) + 3.31'  
 (USE +3.3')

Project NON-FEDERAL DAMS INSPECTION

Sheet D-5 of 16

Computed By HLH

Checked By CEI

Date 6/22/79

Field Book Ref.

Other Refs. CE # 27-660-KA

Revisions

MACBY LAKE DAM #1

2. a. (cmt'd) CLASSIFICATION OF DAM ACCORDING TO FED-ACE GUIDELINES.

(ii) CLASSIFICATION:

SIZE: SMALL

HAZARD: HIGH

b)  $SDF = PHF = 2900 \text{ CFS}$

$\frac{1}{2} PHF = 1450 \text{ CFS}$

3) SURCHARGE AT PEAK INFLOWS


a) PEAK INFLOW:  $Q_p = 2900 \text{ CFS}$

$Q_p' = \frac{1}{2} PHF = 1450 \text{ CFS}$

b) SPILLWAY (OUTFLOW) RATING CURVE

c) SPILLWAY:

MACBY LAKE DAM #1 SPILLWAY IS CLASSIFIED AS A BROAD-CRESTED WEIR OF TRAPEZOIDAL CROSS SECTION WITH  $\frac{1}{4}$  INCLINED FACE (CONCRETE & STONE PAVED) ON  $(\pm) 4"$  TO  $1"$  SLOPE. THE CREST IS  $3'$  BROAD AND  $21.5'$  LONG. THE CENTRAL  $(\pm) 15.5'$  OF



THE SPILLWAY CREST ARE AT ELEV. 133.3' MSL (130' MHW) THE REMAINING  $3'$  AT EACH SIDE BAY  $0.5'$  TO  $(\pm) \text{ELEV. } 133.8' \text{ MSL AT THE SIDE WALLS.}$

THE SLOPING  $\frac{1}{4}$ "

PORTION OF THE WEIR IS CROSSED OVER BY A BRIDGE WITH PIPE RAILINGS. THE DECK, SUPPORTED BY 4 I-BEAMS IS  $(\pm) 1.2'$  THICK.



Project NON-FEDERAL DAMS INSPECTIONSheet 1-6 of 16Computed By HLLChecked By CWDate 6/22/79

Field Book Ref. \_\_\_\_\_

Other Refs. CE #27-610-KA

Revisions \_\_\_\_\_

MALBY LAKE DAM #13.6 - (Cont'd) OUTFLOW RATING CURVE

THE SPILLWAY DISCHARGES INTO A CHANNEL & CULVERT SYSTEM WHICH CARRIES THE FLOW FIRST, PARALLEL AND LATER, ACROSS RTE 34. THE CHANNEL AND CULVERT HEADWALL ARE LOW WITH RESPECT TO THE SPILLWAY CREST AND THEREFORE WILL NOT INTERFERE WITH THE SPILLWAY DISCHARGE, EVEN IF THEIR CAPACITY IS EXCEEDED. (DATA FROM N.H.N.C. DRAWINGS AND C.E. FIELD SURVEY AND OBSERVATIONS).

ASSUME A SPILLWAY DISCHARGE COEFFICIENT  $C=3.0$ . IT IS CONSIDERED THAT THIS COEFFICIENT ACCOUNTS FOR THE INTERFERENCE THAT THE BRIDGE DECK / RAILING MAY OPPOSE TO THE FLOW.

USING THE CREST ELEVATION AS DATUM (ELEV. 133.3' MSL), THE SPILLWAY DISCHARGE IS APPROXIMATED BY:

$$Q_s \approx \underline{65 H^{3/2}}$$

(ii) EXTENSION OF RATING CURVES FOR SURCHARGE HEADS ABOVE TOP OF DAM.

THE DAM IS A GRAVITY MASONRY DAM AND  $\frac{1}{2}$ 'S EARTH EMBANKMENT. THE TOP WIDTH OF THE COMBINED SECTION VARIES FROM (±) 26' TO (±) 36'; THE TOP WIDTH OF THE MASONRY SECTION ALONE IS 8' AND IS CAPPED BY A 3' WIDE, 15" THICK STONE LEDGE AND EARTH FILL. THE  $\frac{1}{2}$ 'S SLOPE OF THE EARTH EMBANKMENT IS (±) 1.5" TO 1" AND THE  $\frac{1}{2}$ 'S FACE OF THE MASONRY WALL IS ON (±) 1" TO 4" SLOPE. TO THE RIGHT OF THE SPILLWAY A MASONRY WING WALL EXTENDS  $\frac{1}{2}$ 'S FOR (±) 85'. THE DAM, EXCLUDING THE SPILLWAY IS (±) 160'. TOP ELEV. 1

Project NON-FEDERAL DAMS INSPECTION

Sheet D-7 of 16

Computed By HEP

Checked By CE

Date 6/25/79

Field Book Ref. \_\_\_\_\_



Other Refs. CE 7-27-660-KA

Revisions \_\_\_\_\_

## MALBY LAKE DAM #1

### 3.6 - Cont'd.) OUTFLOW RATING CURVE

OF DAM AND WING WALL IS (+) 137.3' MSL (134' MNN). THE TOTAL HORIZONTAL LENGTH AT THIS ELEVATION IS (+) 260' AND THE TERRAIN TO THE LEFT OF THE DAM RISES (IN A 5" TO 1" SLOPE). TO THE RIGHT OF THE WING WALL THE TERRAIN RISES AND FALLS FORMING A SERIES OF SWALES, TWO OF WHICH MAY BE SUFFICIENTLY LOW SO AS TO ALLOW AT EXPECTED SURCHARGES, SOME OVERFLOW. (SEE SKETCH OF OVERFLOW PROFILE BELOW). FURTHER, APPROX. 540' OF THE RTE 34 EMBANKMENT THAT CROSSES THE LAKE WILL BE OVERTOPPED AT WL. HIGHER THAN (+) U.S. ELEV. 138.6' MSL (135.3' MNN). ALTHOUGH, IN GENERAL, THE EFFECT OF RTE 34 ON THE PERFORMANCE OF THE DAM AT TEST FLOOD CONDITIONS WILL NOT BE STUDIED, THE OVERTOPPING OF THIS PORTION OF ROAD IS ASSUMED TO BE AN IMPORTANT OUTFLOW OF THE RESERVOIR ABOVE EL. 138.6' MSL WHICH WILL DRAIN TO COVE RIVER PK FROM THE DAM AND THEREFORE, IT WILL BE INCLUDED IN THE OUTFLOW RATING CURVE. THE SIDE SLOPES OF THE DAM,



Project NON-FEDERAL DAMS INSPECTION

Sheet 28 of 16

Computed By HU

Checked By CRG

Date 6/25/79

and Book Ref.

Other Refs. CE # 27-660-KA

Revisions

### MALBY LAKE DAM #1

### 3.6-Cont'd) OUTFLOW RATING CURVE

THE ROAD AND SWALES ARE MOSTLY WOODED MAINLY WITH EVER-GREENS.

ASSUME  $C=3.0$  FOR THE OVERFLOW AT THE DAM AND WING WALL.

$C=2.7$  FOR THE OVERFLOW AT THE HIGHWAY

$C=2.5$  FOR THE WOODED TERRAIN.

ASSUME ALSO, EQUIVALENT LENGTHS FOR THE SLOPING TERRAIN AT THE SIDES OF THE DAM, SWALES AND HIGHWAY, THE FOLLOWING FORMULAS ARE DEVELOPED TO APPROXIMATE THE OUTFLOW (SEE PROFILE SKETCH ON PREVIOUS PAGE):

1') TOP OF DAM/WINGWALL:  $L_0 = 260'$   $\therefore Q_0 = 780 (H-4)^{3/2}$

2') LEFT AND RIGHT SIDES OF DAM/WINGWALL:

$$(L'_{L,R})_1 = \frac{2}{3}(5+9)(H-4) = 9.33(H-4) \quad \therefore (Q'_{L,R})_1 = \frac{23(H-4)^{5/2}}{\text{FOR } H \leq 9'}$$

3') LEFT AND RIGHT SIDES OF LOW SWALE:

$$(L'_{L,R})_2 = \frac{2}{3}(23+30)(H-3.1) = 35.3(H-3.1) \quad \therefore (Q'_{L,R})_2 = \frac{88(H-3.1)^{5/2}}{\text{FOR } H \leq 9'}$$

4') LEFT AND RIGHT SIDES OF HIGHER SWALE:

$$(L'_{L,R})_3 = \frac{2}{3}(14+23)(H-5.7) = 24.7(H-5.7) \quad \therefore (Q'_{L,R})_3 = \frac{62(H-5.7)^{5/2}}{\text{FOR } H \leq 9'}$$

Project NON-FEDERAL DAMS INSPECTION

Sheet 29 of 16

Computed By HILL

Checked By CVG

Date 6/25/79

Field Book Ref. \_\_\_\_\_

Other Refs CE # 27-660-KA

Revisions \_\_\_\_\_

HALEY LAKE DAM #1

3.6, (c-Cont'd) OUTFLOW RATING CURVE

5') RTE 34 LOW GRADE SECTION AT (1) EL. 138.6' MSL

$$L_{R0} = 540' \therefore Q_{R0} = 1550 (H - 5.3)^{3/2}$$

6') LEFT AND RIGHT SIDES OF RTE 34 LOW GRADE

$$(L'_{LR})_1 = \frac{2}{3} (25 + 74) (H - 5.3) = 66 (H - 5.3) \therefore (Q'_{LR})_1 = \frac{165 (H - 5.3)^{3/2}}{\text{FOR } H \leq 11.7'}$$

THEREFORE THE TOTAL OUTFLOW RATING CURVE CAN BE APPROXIMATED BY:

$$Q_T = Q_S + Q_{R0} + (Q'_{LR})_1 + (Q'_{LR})_2 + (Q'_{LR})_3 + Q_{R0} + (Q'_{LR})_4$$

FOR H ≤ 9'

THE RESULTING OUTFLOW RATING CURVE IS PLOTTED ON NEXT PAGE.

### C) SPILLWAY CAPACITY

IT SHOULD BE NOTED THAT THE SWALE CLOSEST TO THE RIGHT OF THE DAM IS AT ITS LOW POINT (1) EL. 136.4' MSL LOWER THAN THE DAM.

THEREFORE, UNLESS IT IS RAISED TO AT LEAST ELEV. 137.8' MSL, THERE WILL BE SOME OVERFLOW BEFORE THE TOP OF THE DAM IS REACHED

THE SPILLWAY CAPACITY IS THEN:

i) TO THE SWALE LOW POINT ELEV. 136.4' MSL

$$H = 3.1' \therefore Q_{S1} = 350 \text{ cfs } (\approx) 12\% \text{ OF } Q_{R0}; (\approx) 24\% \text{ OF } Q_T$$



Project NON-FEDERAL DAMS INSPECTION

Sheet D-10 of 16

Computed By HLL

Checked By CE

Date 6/25/79


Field Book Ref. \_\_\_\_\_

Other Refs. CE #27-660-KA

Revisions \_\_\_\_\_

### MALBY LAKE DAM #1

### 3. Cont'd) OUTFLOW RATING CURVE



● SEE NOTE P. 4 OF THESE COMPUTATIONS

### C-Cont'd) SPILLWAY CAPACITY

(i) TO TOP OF DAM (ASSUMING NO LOW SWALE OVERTFLOW):

$$H = 4' \therefore Q_s'' = 520 \text{ CFS } ((\pm) 18\% \text{ OF } Q_p; (\pm) 36\% \text{ OF } Q_p')$$

\* SEE P. 6 OF THESE COMPS.

(ii) TO TOP OF DAM INCLUDING SWALE OVERTFLOW:

$$H = 4' \therefore Q_s''' = 590 \text{ CFS } ((\pm) 20\% \text{ OF } Q_p; (\pm) 41\% \text{ OF } Q_p')$$



Project NON-FEDERAL DAMS INSPECTION

Sheet D-11 of 16

Designed By HU

Checked By CRG

Date 6/25/79

Book Ref.

Other Refs. CE #27-566-KA

Revisions

MANTBY LAKE DAM #1

3-Cont'd) SURCHARGE AT PEAK INFLOWS:

d) SURCHARGE HEIGHT TO PASS  $Q_p$ :

i) @  $Q_p = PMF = 2900 \text{ cfs}$   $H_1 = 5.4'$

ii) @  $Q_p' = \frac{1}{2} PMF = 1450 \text{ cfs}$   $H_1' = 4.7'$

A) EFFECT OF SURCHARGE STORAGE ON MAXIMUM PROBABLE DISCHARGES (OUTFLOW)

a) RESERVOIR (LAKE) AREA @ FLOW LINE: \*  $A = 229 \text{ ac}$

$\therefore$  ASSUME AVE LAKE AREA WITHIN EXPECTED SURCHARGE, \*  $\bar{A} = 25 \text{ ac}$

\* SEE "STORAGE" ON A-4 OF THESE COMPUTATIONS. NO SUBSTANTIAL AREA/STORAGE INCREMENT FROM THE LAKE PORTIONS SEPARATED BY THE ROAD IS CONSIDERED.

b) ASSUME NORMAL POOL LEVEL (1) 0.2' ABOVE SPURWAY CREST (EL 133.54)

c) WATERSHED AREA:  $DA = 1.29 \text{ sq mi}$  (See p. 3 OF THESE COMPS.)

d) DISCHARGE ( $Q_p$ ) AT VARIOUS HYPOTHETICAL SURCHARGE ELEVATIONS:

$H = 6'$   $V = 25 \times (6 - 0.2) = 145 \text{ ac-ft}$   $S = \frac{145}{1.29 \times 53.3} = 2.11''$

$H = 3'$   $V = 70 \text{ ac-ft}$   $\therefore S = 1.02''$

Project NON-FEDERAL DAMS INSPECTIONSheet D-12 of 16Computed By HMMChecked By CEDate 6/26/79

and Book Ref

Other Refs CE # 27-660-KA

Revisions

MALBY LAKE DAM #1A.1-CMTD) EFFECT OF SURCHARGE ON PEAK OUTFLOW - ( $Q_p$ )

FROM APPROXIMATE STORAGE ROUTING NED-ACE GUIDELINES (19" MAX. PROBABLE R.O. IN NEW ENGLAND):

$$Q_p = Q_p' \left(1 - \frac{S}{19}\right) \text{ AND FOR } \frac{1}{2} \text{ PMF: } Q_p' = Q_p' \left(1 - \frac{S}{19}\right)$$

FOR THE PREVIOUS HYPOTHETICAL DISCHARGES:

$$H = 6' \quad Q_p = 2580 \text{ cfs} \quad Q_p' = 1130 \text{ cfs}$$

$$H = 3' \quad Q_p = 2750 \text{ cfs} \quad Q_p' = 1300 \text{ cfs}$$

$$\text{ALSO, FOR } H = 0.2; \quad Q_p = 2900 \text{ cfs} \text{ AND } Q_p' = 1450 \text{ cfs}$$

e) PEAK OUTFLOW ( $Q_p$ ).

USING NED-ACE GUIDELINES "SURCHARGE STORAGE ROUTING" ALTERNATE METHOD (SEE P. 10 OF THESE COMPUTATIONS):

$$Q_p = 2620 \text{ cfs} \quad H_3 = 5.3' \text{ FOR } Q_p = \text{PMF}$$

$$Q_p' = 1220 \text{ cfs} \quad H_3' = 4.6' \text{ FOR } Q_p' = \frac{1}{2} \text{ PMF}$$

f) SPILLWAY CAPACITY RATIO TO OUTFLOW:

$$i) \text{ SPILLWAY CAPACITY* TO THE SMALL LOW POINT: } Q_s' = 350 \text{ cfs}$$

THE SPILLWAY CAPACITY IS (1) 13% THE OUTFLOW AT PMF (TEST FLOOD) AND (2) 29% THE OUTFLOW AT  $\frac{1}{2}$  PMF.

\* SEE PP. 9 & 10 OF THESE COMPUTATIONS

Project NON-FEDERAL DAMS INSPECTION

Sheet D-13 of 16

Computed By HLL

Checked By CPH

Date 6/26/79

Book Ref. \_\_\_\_\_

Other Refs CE # 27-660-KA

Revisions \_\_\_\_\_

### HACTBY LAKE DAM #1

#### 4. f - (cont'd) EFFECT OF SURCHARGE ON PEAK OUTFLOW - SPILL CAP. AT $Q_3$

(ii) SPILLWAY CAPACITY TO TOP OF DAM (ASSUMING NO SWALE OVERFLOW)  
IF THE LOW POINT AT THE RIGHT OF THE DAM IS CLOSED, THERE WILL BE A SLIGHT (NEGLECTIBLE) INCREASE IN SURCHARGE AND A CONSEQUENT NEGLECTIBLE REDUCTION IN  $Q_2$  AND  $Q_3'$ . THE SPILLWAY CAPACITY TO TOP OF THE DAM WOULD BE:  $Q_3' \approx 520$  CFS OR, (±) 20% THE OUTFLOW AT PMF AND (±) 43% THE OUTFLOW AT ½ PMF

(iii) SPILLWAY CAPACITY TO TOP OF DAM INCLUDING THE SWALE OVERFLOW:  
 $Q_3'' \approx 590$  CFS OR, (±) 23% THE OUTFLOW AT PMF AND (±) 48% THE OUTFLOW AT ½ PMF

### 5) SUMMARY

a) PEAK INFLOW:  $Q_1 = \text{PMF} = 2900$  CFS  $Q_1' = \frac{1}{2} \text{PMF} = 1450$  CFS

b) PEAK OUTFLOW:  $Q_2 = 2620$  CFS  $Q_2' = 1220$  CFS

c) SPILLWAY CAPACITY TO FIRST POINT OF OVERFLOW (SWALE):  $Q_3 \approx 350$  CFS OR, (±) 13% OF  $Q_2$  AND (±) 29% OF  $Q_3'$  (SEE 4. f P. 13 AND ABOVE)

THEREFORE AT SDF = PMF THE DAM IS OVERTOPPED (±) 1.3' (U.S. EL. 138.6' NSL = 135.3' MNN) OR, TO A SURCHARGE OF (±) 5.3' ABOVE THE SPILLWAY CREST. AT THIS CONDITION, THE OVERFLOW AT THE LOW SWALE IS (±) 630 CFS AND (±) 2.2' DEEP.

AT TEST FLOOD  $Q_2' = \frac{1}{2} \text{PMF}$  THE DAM IS OVERTOPPED (±) 0.6' (U.S. EL. 137.9' NSL = 134.6' MNN) OR, TO A SURCHARGE OF (±) 4.6' ABOVE THE SPILLWAY CREST. THE SWALE OVERFLOW IS (±) 290 CFS AT A DEPTH OF (±) 1.5'

Project NON-FEDERAL DAMS INSPECTION

Sheet D-14 of 16

Designed By HML

Checked By CE#

Date 6/26/79

Book Ref. \_\_\_\_\_

Other Refs. CE# 27-660-KA

Revisions \_\_\_\_\_

MALBY LAKE DAM #1

### II) DOWNSTREAM FAILURE HAZARD

#### 1) PEAK FLOOD AND STAGE IMMEDIATELY D/S FROM DAM:

##### a) BREACH WIDTH:

i) MID-HEIGHT ( $\pm$ ) ELEV 124.3' MSL (121' MHW)  $(137.3 - \frac{*26}{2} = 124.3' \text{ MSL})$

\* SEE HEIGHT P. 4 OF THESE (DAMS)

ii) APPROX. MID-HEIGHT LENGTH:  $L = 160'$  (\* C.E. MEASURE ON N.H.W. CO. DWS

Nº 30007 AND H.W. DIST. 1" = 100' MAP, 3/4")

iii) BREACH WIDTH (SEE NED-ACE P/S DAM FAILURE GUIDELINES):

$$W = 0.4 \times 160 = 64' \quad \therefore \text{ASSUME } W_b = 60'$$

#### b) PEAK FAILURE OUTFLOW ( $Q_p$ ):

ASSUME SURCHARGE TO TOP OF DAM (EL. 137.3' MSL); THEREFORE,

i) HEIGHT AT TIME OF FAILURE:  $Y_0 = 26'$

ii) SPILLWAY DISCHARGE:  $Q_s = 520 \text{ CFS}$  (SEE P. 10 OF THESE (DAMS))

iii) BREACH OUTFLOW ( $Q_b$ ):

$$Q_b = \frac{8}{27} W_b \sqrt{Y_0} Y_0^{3/2} = 13400 \text{ CFS}$$

iv) PEAK FAILURE OUTFLOW ( $Q_p$ ):  $Q_p = Q_s + Q_b = 13900 \text{ CFS}$

#### c) FLOOD DEPTH IMMEDIATELY D/S FROM DAM:

$$Y = 0.44 Y_0 = 11'$$



Project NON-FEDERAL DAMS INSPECTION

Sheet 015 of 16

Prepared By HLL

Checked By CPG

Date 6/26/77

Field Book Ref.

Other Refs. CE #37-660-KA

Revisions

### MACBY LAKE DAM #1

#### 1-Cont'd) PEAK FLOOD AND STAGE IMMEDIATELY D/S FROM DAM

##### a) APPROXIMATE STAGE JUST BEFORE FAILURE

i)  $Q \approx Q_c = 520 \text{ cfs}$

##### ii) CHANNEL D/S FROM DAM:

THE SPILLWAY DISCHARGE IS CONVEYED D/S BY A CULVERT OF VARIOUS CROSS-SECTION UNDER RTB 34. ESSENTIALLY THE CULVERT HAS 3 REACHES: a)  $L=119'$ , 10' W X 5' H BOX; b)  $L=50'$ , 10' B X 5' H ARCH; AND  $L=205'$ , 8' W X 5' H BOX. THE GROUND ELEV. @ HEADWALL IS (+) EL. 118' MSL; THE INVERT ELEV.

AT THE OUTLET IS AT ELEV. 100.6' MSL. ASSUMING  $n=0.015$ , THE CONVEYANCES OF THE 3 SECTIONS ARE RESPECTIVELY,  $K_1=7000$

$K_2=6300$ ;  $K_3=5300$ . THEREFORE, ASSUMING THE TAILWATER AT EL. 106' MSL ( $\pm$  TOP OF CULVERT) AND ENTRANCE ( $K_e=0.5$ )

OUTLET ( $K_o=1$ ) AND TRANSITION LOSSES ( $K_{t1}=0.3$ ) THE CULVERT CAPACITY CAN BE APPROXIMATED BY:

$$Q_c \approx 210 (H + 12)^{0.5}$$

WHERE  $H$  (POSITIVE OR NEGATIVE) IS THE SURCHARGE ABOVE THE HEADWALL (GROUND EL. 118' MSL).

$\therefore$  FOR  $H=0$ ,  $Q_c \approx 730 \text{ cfs}$  CULVERT CAPACITY w/o OVERFLOW

THEREFORE, THE CULVERT CAN CARRY THE SPILLWAY DISCHARGE ( $Q_c=520 \text{ cfs}$ ) WITH (+) 6' FREEBOARD (CONDITION JUST BEFORE FAILURE).



Object NON-FEDERAL DAMS INSPECTION

Sheet D-16 of 16

Computed By HLL

Checked By CPG

Date 6/27/79

Old Book Ref.

Other Refs. CE #27-650-KA

Revisions

### MALBY LAKE DAM #1

#### 1-Cont'd) PEAK FLOOD AND STAGE IMMEDIATELY $\frac{D}{S}$ FROM DAM

##### c) RAISE IN STAGE AFTER FAILURE

i)  $Q = Q_R = 13900 \text{ cfs}$

##### ii) FLOODWAY $\frac{D}{S}$ FROM DAM:

THE GROUND ABOVE THE CULVERT (RTE 34 AND IMMEDIATE IMPACT AREA) FORMS A FLOODWAY ROUGHLY OF TRAPEZOIDAL CROSS SECTION, (T) 130' AT THE BASE AND 18" TO 1" AND 3" TO 1" SIDE SLOPES. THE GROUND SLOPES  $\frac{D}{S}$  AT (T)  $S = 2.4\%$ . ASSUMING  $N = 0.025$ , THE FLOW WILL DIVIDE (ROUGHLY) BETWEEN THE CULVERT, (T) 800 cfs, AND THE FLOODWAY, (T) 13100 cfs. ASSUMING THIS STEADY-STATE TO REPRESENT THE CONDITIONS AFTER THE DAM FAILURE, THE FLOOD DEPTH ABOVE GROUND WILL BE APPROXIMATELY,  $y = 4'$

#### 2) SUMMARY

a) PEAK FAILURE OUTFLOW:  $Q_R = 13900 \text{ cfs}$

b) FLOOD DEPTH IMMEDIATELY  $\frac{D}{S}$  FROM DAM:  $y_0 = 11'$

##### c) APPROX. FLOOD DEPTH ABOVE GROUND AFTER

FAILURE AT IMMEDIATE IMPACT AREA:  $y = 4'$

PRELIMINARY GUIDANCE  
FOR ESTIMATING  
MAXIMUM PROBABLE DISCHARGES  
IN  
PHASE I DAM SAFETY  
INVESTIGATIONS

New England Division  
Corps of Engineers

March 1978

MAXIMUM PROBABLE FLOOD INFLOWS  
NED RESERVOIRS

<u>Project</u>	<u>Q</u> (cfs)	<u>D.A.</u> (sq. mi.)	<u>MPF</u> cfs/sq. mi.
1. Hall Meadow Brook	26,600	17.2	1,546
2. East Branch	15,500	9.25	1,675
3. Thomaston	158,000	97.2	1,625
4. Northfield Brook	9,000	5.7	1,580
5. Black Rock	35,000	20.4	1,715
6. Hancock Brook	20,700	12.0	1,725
7. Hop Brook	26,400	16.4	1,610
8. Tully	47,000	50.0	940
9. Barre Falls	61,000	55.0	1,109
10. Conant Brook	11,900	7.8	1,525
11. Knightville	160,000	162.0	987
12. Littleville	98,000	52.3	1,870
13. Colebrook River	165,000	118.0	1,400
14. Mad River	30,000	18.2	1,650
15. Sucker Brook	6,500	3.43	1,895
16. Union Village	110,000	126.0	873
17. North Hartland	199,000	220.0	904
18. North Springfield	157,000	158.0	994
19. Ball Mountain	190,000	172.0	1,105
20. Townshend	228,000	106.0(278 total)	820
21. Surry Mountain	63,000	100.0	630
22. Otter Brook	45,000	47.0	957
23. Birch Hill	88,500	175.0	505
24. East Brimfield	73,900	67.5	1,095
25. Westville	38,400	99.5(32 net)	1,200
26. West Thompson	85,000	173.5(74 net)	1,150
27. Hodges Village	35,600	31.1	1,145
28. Buffumville	36,500	26.5	1,377
29. Mansfield Hollow	125,000	159.0	786
30. West Hill	26,000	28.0	928
31. Franklin Falls	210,000	1000.0	210
32. Blackwater	66,500	128.0	520
33. Hopkinton	135,000	426.0	316
34. Everett	68,000	64.0	1,062
35. MacDowell	36,300	44.0	825

MAXIMUM PROBABLE FLOWS  
BASED ON TWICE THE  
STANDARD PROJECT FLOOD  
(Flat and Coastal Areas)


<u>River</u>	<u>SPF</u> (cfs)	<u>D.A.</u> (sq. mi.)	<u>MPF</u> (cfs/sq. mi.)
1. Pawtuxet River	19,000	200	190
2. Mill River (R.I.)	8,500	34	500
3. Peters River (R.I.)	3,200	13	490
4. Kettle Brook	8,000	30	530
5. Sudbury River.	11,700	86	270
6. Indian Brook (Hopk.)	1,000	5.9	340
7. Charles River.	6,000	184	65
8. Blackstone River.	43,000	416	200
9. Quinebaug River	55,000	331	330



# MAXIMUM PROBABLE FLOOD


## PEAK FLOW RATES

x5 - NED DAM IDENTIFICATION  
 ⊗ 7' - TWICE-SPF AT INDICATED SIT  
 DEC. 1977





# ESTIMATING EFFECT OF SURCHARGE STORAGE ON MAXIMUM PROBABLE DISCHARGES



**STEP 1:** Determine Peak Inflow ( $Q_{p1}$ ) from Guide Curves.

**STEP 2:** a. Determine Surcharge Height To Pass " $Q_{p1}$ ".

b. Determine Volume of Surcharge ( $STOR_1$ ) In Inches of Runoff.

c. Maximum Probable Flood Runoff In New England equals Approx. 19", Therefore

$$Q_{p2} = Q_{p1} \times \left(1 - \frac{STOR_1}{19}\right)$$

**STEP 3:** a. Determine Surcharge Height and " $STOR_2$ " To Pass " $Q_{p2}$ "

b. Average " $STOR_1$ " and " $STOR_2$ " and Determine Average Surcharge and Resulting Peak Outflow " $Q_{p3}$ ".

## **SURCHARGE STORAGE ROUTING SUPPLEMENT**

**STEP 3: a. Determine Surcharge Height and  
"STOR<sub>2</sub>" To Pass "Q<sub>p2</sub>"**

**b. Avg "STOR<sub>1</sub>" and "STOR<sub>2</sub>" and  
Compute "Q<sub>p3</sub>".**

**c. If Surcharge Height for Q<sub>p3</sub> and  
"STOR<sub>AVG</sub>" agree O.K. If Not:**

**STEP 4: a. Determine Surcharge Height and  
"STOR<sub>3</sub>" To Pass "Q<sub>p3</sub>"**

**b. Avg. "Old STOR<sub>AVG</sub>" and "STOR<sub>3</sub>"  
and Compute "Q<sub>p4</sub>"**

**c. Surcharge Height for Q<sub>p4</sub> and  
"New STOR<sub>AVG</sub>" should Agree  
closely**

## SURCHARGE STORAGE ROUTING ALTERNATE

$$Q_{p2} = Q_{p1} \times \left( 1 - \frac{\text{STOR}}{19} \right)$$


$$Q_{p2} = Q_{p1} - Q_{p1} \left( \frac{\text{STOR}}{19} \right)$$

FOR KNOWN  $Q_{p1}$  AND 19" R.O.

$Q_{p2}$   
 \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_


STOR  
 \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_

EL.  
 \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_



Q

# "RULE OF THUMB" GUIDANCE FOR ESTIMATING DOWNSTREAM DAM FAILURE HYDROGRAPHS



**STEP 1:** DETERMINE OR ESTIMATE RESERVOIR STORAGE (S) IN AC-FT AT TIME OF FAILURE.

**STEP 2:** DETERMINE PEAK FAILURE OUTFLOW ( $Q_{p1}$ ).

$$Q_{p1} = \frac{8}{27} W_b \sqrt{g} Y_0^{3/2}$$

$W_b$  = BREACH WIDTH - SUGGEST VALUE NOT GREATER THAN 40% OF DAM LENGTH ACROSS RIVER AT MID HEIGHT.

$Y_0$  = TOTAL HEIGHT FROM RIVER BED TO POOL LEVEL AT FAILURE.

**STEP 3:** USING USGS TOPO OR OTHER DATA, DEVELOP REPRESENTATIVE STAGE-DISCHARGE RATING FOR SELECTED DOWNSTREAM RIVER REACH.

**STEP 4:** ESTIMATE REACH OUTFLOW ( $Q_{p2}$ ) USING FOLLOWING ITERATION.

A. APPLY  $Q_{p1}$  TO STAGE RATING, DETERMINE STAGE AND ACCOMPANYING VOLUME ( $V_1$ ) IN REACH IN AC-FT. (NOTE: IF  $V_1$  EXCEEDS  $1/2$  OF S, SELECT SHORTER REACH.)

B. DETERMINE TRIAL  $Q_{p2}$ .

$$Q_{p2}(\text{TRIAL}) = Q_{p1} \left(1 - \frac{V_1}{S}\right)$$

C. COMPUTE  $V_2$  USING  $Q_{p2}(\text{TRIAL})$ .

D. AVERAGE  $V_1$  AND  $V_2$  AND COMPUTE  $Q_{p2}$ .

$$Q_{p2} = Q_{p1} \left(1 - \frac{V_{\text{avg}}}{S}\right)$$

**STEP 5:** FOR SUCCEEDING REACHES REPEAT STEPS 3 AND 4.

APRIL 1978

APPENDIX E

INFORMATION AS CONTAINED IN  
THE NATIONAL INVENTORY OF DAMS



# INVENTORY OF DAMS IN THE UNITED STATES

STATE	DIVISION	STATE COUNTY DIST.	CONGR. STATE COUNTY DIST.	NAME	LATITUDE (NORTH)	LONGITUDE (WEST)	REPORT DATE DAY   MO   YR
CT	111 NED	CT 009 03		MALTBY LAKE DAM NUMBER 1	4110.3	7258.3	31 AUG 79

POPULAR NAME		NAME OF IMPOUNDMENT	
		MALTBY LOWER LAKE	
REGION BASIN	RIVER OR STREAM	NEAREST DOWNSTREAM CITY - TOWN - VILLAGE	POPULATION
01 07	TR-WEST RIVER	WEST HAVEN	53600

TYPE OF DAM	YEAR COMPLETED	PURPOSES	STRAIC HYDRAU. HEIGHT (FT.)		IMPOUNDING CAPACITIES (ACRE-FT.)		DIST. FROM DAM (MI.)	POPULATION
			MAXIMUM	NORMAL	MAXIMUM	NORMAL		
REPG	1862 S		28	26	260	161	3	53600

DIST. OWN FED R PRV/FED SCS A VER/DATE  
NED N N N : N

REMARKS	
22-GRAVITY SECTION IN 1900	

D/S HAS	SPILLWAY CREST LENGTH	TYPE	WIDTH (FT.)	VOLUME OF DAM (CY)	POWER CAPACITY INSTALLED (KW)	PROPOSED (KW)	NAVIGATION LOCKS LENGTH (FT.)	WIDTH (FT.)	DEPTH (FT.)
1	182	U	22	520					

OWNER	ENGINEERING BY	CONSTRUCTION BY
NEW HAVEN WATER COMPANY	ALBERT B HILL	CHARLES W BLAKESLEE

DESIGN		CONSTRUCTION		OPERATION		MAINTENANCE	
CT WATER RESOURCES	CT WATER RESOURCES	CT WATER RESOURCES	CT WATER RESOURCES	CT WATER RESOURCES	CT WATER RESOURCES	CT WATER RESOURCES	CT WATER RESOURCES

INSPECTION BY		INSPECTION DATE DAY   MO   YR		AUTHORITY FOR INSPECTION	
CAMN ENGINEERS INC		01 MAY 79		PL 92-367	

REMARKS	

END

FILMED

8-84

DTIC